ENGINEERING DEPARTMENT

BUILDINGS DIVISION, BANGALORE.

Abstract Notification dated 25th March 1935.

The attention of the public is invited to the Notification calling for the tenders for conctin the Quarters for the Superintendent, Central Jail, Bangalore, published on pages 668-6f, P t VI of the *Mysore Gazette*, dated 28th March 1935.

The last date for receiving tenders is 6th April 1935.

Notification dated 1st *April* 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Execu Engineer, Buildings Division, up to 27th April 1935 (2 P.M.) for constructing a Building for locat Arrack and Toddy Shops near the Binny Mills, Bangalore City. An approximate estimate of quities is given below. These quantities are not guaranteed. The work should be completed b e end of October 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engine Office at Bangalore between the hours of 11 A.M. to 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the cutive Engineer. The tenders shuld be accompanied by a statement in the form given below owing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rupees Three hundred only ash or Government Promissory Notes, as earnest money, and be superscribed " Tender for conucting a Building for locating Arrack and Toddy Shops near the Binny Mills in default " of whic enders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer ysore Circle, Mysore, who does not bind himself to accept the lowest or any tender or to assign a reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will b quired to execute the usual contract bond ; in default of which, his tender will be considered celled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be ted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry reg ng the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be urned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule ra of the Department or those fixed by the Executive Engineer after working out data with not re than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about ra quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of t Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in spe term of unit shown against each item of work. Any quotation quoted at so much per cent less or more than estimated rate will not be accepted.

Transfer of work to third parties by selected contractors will not be countenanced by t Department and in the case of any such attempt, the earnest money is liable to be forfeited at the cretion of the Superintending Engineer.

Abstract estimate of quantities for constructing an Arrack shop near Binny Mills area, ngalore.

No.	Items of work	Unit	antity
1	Earth work excavation and filling in basement	C.yd.	49
2	Concrete with broken jelly lime mortar	C.ft.	219
3	Size stone in clay with bond slabs 6′ apart	,,	1,199
4	Burnt brick in clay	,,	2,838
5	Chunam plastering	Sqr.	39.97
6	White and colour washing two coats	,,	39.97
7	Flooring with Cuddappa slabs on 3″ concrete bed and cement pointing	,,	12.50
8	Teak wood battened doors 3″×5″ frame with iron fittings, etc., complete	S.ft.	23
9	Teak wood battened windows with $\frac{3}{4}$″ iron bars, iron fittings, etc., complete	,,	149

No.	Items of work	Unit	Quantity
10	Chacolate painting two coats	Sqr.	3.40
11	Teak wood wrought and put up with wood oiling	C.ft.	128.40
12	Roofing with 1st class Mangalore Tiles on teak reepers complete	Sqr.	19.78
13	Mortar bands over roof	R.ft.	86
14	Teak wood eave boards ¾″ thick 9″ wide including painting, etc., complete as per design	,,	92
15	Burnt stone slabs 6″ thick roughly dressed and fixed in mortar	S.ft.	462
16	Iron trusses 30′ clear span with fixing, etc., complete	Cwt.	15
17	Ridge tiles set in mortar	R.ft.	46
18	Chunam pointing to basement	Sqr.	3.08
	Constructing Toddy Shop.		
1	Earthwork excavation and filling in basement	C.yd.	74
2	Concrete with broken jelly with mortar	C.ft.	584
3	Size stone in clay with bond slabs 6′ apart	,,	1,785
4	Burnt Brick in clay	,,	2,574
5	Chunam plastering	Sqr.	36.19
6	White washing two coats inside and colour washing outside	,,	36.19
7	Flooring with Cuddappa slabs on 3″ concrete bed and cement pointing	,,	11.65
8	Teak wood battened doors 3″×5″ frames with iron fittings, etc., complete	S.ft.	46
9	Teak wood windows battend with ¾″ iron bars, iron fittings, etc., complete	,,	96
10	Chacolate paintng two coats	Sqr.	2.70
11	Pucca terrace	,,	1.50
12	Teak wood wrought and put up	C.ft.	99.50
13	Roofing with 1st class Mangalore Tiles on teak reepers, etc., complete	Sqr.	14.26
14	Mortar bands over roof	R.ft.	62
15	Teak wood eave board ¾″ thick 9″ deep with painting, etc., complete as per design	,,	154
16	Burnt stone slabs 6″ thick roughly dressed	S.ft.	178
17	Cornice Work	R.ft.	35
18	Parapet wall with plastering, etc., complete	,,	35
19	Coping of compound wall	,,	35
20	Iron trusses 30′ clear span hoisting, etc., complete	Cwt.	4.37
21	Down water pipes with 3″ diameter zinc sheet including fixing, etc., complete	R.ft.	20
22	Pointing to basement alround with lime mortar	Sqr.	2.31
23	Teak wood finials	Each	2
24	Teak wood pendants	,,	4
25	Ridge tile set in mortar	R.ft.	46

Notification dated 1st April 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 27th April 1935 (2 P.M.) for constructing a Building for the Boys' Scouts Head-quarters Office, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rupees Five hundred only in Cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Building for the Boy Scout Headquarters Office, Bangalore" in default of which, tender will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Mysore Circle, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department of those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engin er will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much per centage less or more than estimated rate will not be accepted.

Transfer of work to third parties by selected contractors will not be countenanced by the Department and in the case of any such attempt, the earnest money is liable to be forfeited at the discretion of the Superintending Engineer.

Abstract estimate of quantities for constructing Building for Boy Scouts Head-quarters Office, Bangalore.

No.	Items of work	Per	Quantity
1	Earthwork excavation foundation and filling in basement ..	C.yd.	418
2	Stone jelly concrete in Lime mortar 1 : 2 : 3	C.ft.	2,890
3	Size stone in mortar with bond stones at 6′ apart for foundation ..	,,	4,892
4	Do do basement	,,	2,142
5	Burnt Brick in mortar	,,	4,723
6	Burnt stone slabs 6″ thick exposed surfaces two lines dressed and fixed	S.ft.	1,069
7	Arch work brick in mortar	C.ft.	632
8	Teak wood windows ¾″ iron bars half panelled and half glazed shutters parliamentary hinges, etc., complete	S.ft.	154
9	Teak wood doors panelled shutters parliamentary hinges, etc., complete	,,	336
10	Semicircular glazed ventilators	,,	115
11	Stone pillars nicely dressed with base and capitals front verandah ..	Each	8
12	Half pillars do	,,	2
13	Rolled steel girders including hoisting, boxing, etc., complete ..	Cwt.	86.17
14	Rolled steel joists including fixing and painting	,,	17.16
15	Stone wall plate 3 to 4″ thick including fixing	S.ft.	273
16	Pucca terrace work complete	Sqr.	25.21
17	Ornamental cornice work as per plan	R.ft.	136
18	Chunam plastering	Sqr.	72.67
19	Cement pointing to basement	,,	8.10
20	Flooring with Mangalore Tiles on 3″ concrete and cement pointing ..	,,	19.28
21	White and colour washing	,,	72.67
22	Parapet wall alround as per design in plan	R.ft.	250
23	Silicate painting three coats	Sqr.	12.10
24	Rain water down pipes	R.ft.	..

A. TANDONI RAO,
Executive Engineer.